

**SECTION 6B**

**STORM DRAIN - INSTALLATION**

- 6B.1 Scope
- 6B.2 General
- 6B.3 Pipe Installation
- 6B.4 Manhole, Cleanout and Catchbasin Installation
- 6B.5 Service Connection Installation
- 6B.6 Notification to the Town of Ladysmith
- 6B.7 Cleaning and Flushing
- 6B.8 Video Inspecting Mains
- 6B.9 Manhole Testing
- 6B.10 Smoke Testing
- 6B.11 Pipe Condition Report Format

**STANDARD DRAWINGS**

D1	Manhole Benching Details
D2	Typical Manhole Details
D2A	Precast Riser Manhole
D3	Typical Precast Drop Manhole Details
D3A	Inside Drop Manhole
D4	Heavy Duty Manhole Cover and Frame
D4A	Utility Chamber Manhole Frame, Ring & Cover
D5	Sanitary and Storm Sewer Connection
D6	Driveway Service Box Installation
D7	Single Service Concrete Box
D8	Twin Service Concrete Box
D9	Cleanout Structure - Type 1
D10	Cleanout Structure - Type 2
D11	Typical Catch Basin - Type 1 & Type 2
D12	Catch Basin Frame and Grate - Type 1
D12A	Catch Basin Frame and Grate - Type 2
D13	Side Inlet Catch Basin For Non Mountable Curbs - Type 3
D13A	Side Inlet Frame & Hood For Non Mountable Curbs - Type 3
D14	Ditch Inlet Catch Basin - Type 4
D14A	Frame and Grate for Ditch Inlet Catch Basin - Type 4
D15	Concrete Headwall for Pipe Inlets – Type 1
D15A	Concrete Headwall for Pipe Inlets – Type 2
D16	Concrete Headwall for Pipe Outlets
D17	Rainfall curves
D18	Time of Concentration Table
D19	Storm Sewer Flow Analysis Calculation Sheet

**SECTION 6B****STORM DRAIN - INSTALLATION****6B.1 SCOPE**

This section shall govern the installation of all storm drains and their appurtenances within the Municipality.

**6B.2 GENERAL**

6B.2.1 Provision shall be made to maintain the flow of all drains, ditches, watercourses and service connection that may be encountered during the progress of the work. Where existing systems are anticipated or located during construction, the existing system shall be connected to the new installation or replaced. In every case the contractor and/or Consulting Engineer shall notify the Municipality when previously unidentified systems are found. The contents of any sewer, drain or service connection shall not be allowed to flow into the trench or into the main.

6B.2.2 The Contractor shall ensure debris and mortar droppings do not enter any part of the storm drain system and shall leave all pipe lines, manholes, silt traps, cleanouts, catch basins and other appurtenances in a thoroughly clean condition.

6B.2.3 Any connection or modification to existing works shall be by Municipal crews at the Developer's expense, unless specifically approved otherwise.

6B.2.4 Any work in or about natural watercourses, creeks, rivers, lakes or oceans shall be carried out in accordance with the requirements of the Ministry of Environment and/or Federal Fisheries.

**6B.3 PIPE INSTALLATION**

6B.3.1 Standards for excavation, bedding, backfilling and restoration shall be in accordance with Section 3.

6B.3.2 Pipe shall be checked before being lowered into the trench to ensure that no foreign material, manufacturer's defects, or cracks exist that might prevent the proper jointing of the pipe or its operation.

6B.3.3 Pipes shall be handled, stored and laid in accordance with the recommendations of the pipe manufacturer and in all cases gaskets shall be installed. Particular care shall be taken to ensure that before each joint is made the pipe is cleaned out and all dirt and other debris removed.

6B.3.4 Pipe laying shall commence at the lowest point of the length being laid and the pipes shall be placed with spigot ends pointing in the direction of flow.

6B.3.5 The open end of the pipe in the trench shall be suitably covered to prevent entrance of trench water and other material during periods when pipe is not being installed.

6B.3.6 Precautions shall be taken to ensure that displacement of the pipe in the trench does not occur through soil displacement or floatation due to the presence of trench water. Pipe that has been

displaced shall be removed from the trench and re-laid.

6B.3.7 Pipe shall not be backfilled until the bedding, grade and alignment has been approved by the Consulting Engineer.

6B.3.8 The pipe shall be laid on the alignment and grade in accordance with the construction drawings. Methods to maintain pipe alignment and grade must be approved by the Engineer. Each pipe shall be checked for line and grade as it is installed.

6B.3.9 Unless otherwise directed by the Engineer, tolerances for pipe alignment and grade shall be:

Alignment	=	± 50 mm
Grade	=	± 10 mm

6B.3.10 Where a storm drain is being constructed as an extension to an existing Municipal system, gravel traps must be installed by the contractor. Alternatively, the Engineer may require that the existing pipe remain sealed until the sewer extension is completed, flushed, tested and accepted by the Municipality. Upon acceptance, the seal may be removed and one length of pipe installed to connect the extension to the existing system.

6B.3.11 Where storm drains and sanitary sewers are installed in a common trench, there shall be a minimum 300 mm lateral clearance between the walls of adjacent pipes. Where deflections are required to accommodate manholes or other works, only the storm drain shall be deflected from the approval alignment.

#### 6B.4 **MANHOLE, CLEANOUT AND CATCH BASIN INSTALLATION**

Unless otherwise approved by the Engineer, all manhole bases shall be precast concrete.

##### 6B.4.1 Manhole Concrete Bases

- (a) All water shall be removed from the excavation prior to placing base concrete. The base shall be constructed such that the first section of a precast section can be set plumb with uniform bearing throughout its full circumference.
- (b) If material in the bottom of the trench is unsuitable for support, the bottom shall be over excavated to firm base as determined by the Consulting Engineer and backfilled to the required grade with thoroughly compacted base gravel as specified for unstable sub-grade in Section 3 Trenching, Backfilling and Restoration.
- (c) Concrete manhole bases shall be constructed as shown on the drawings. Pipes and fittings through the manhole shall be supported on concrete blocks and the concrete base poured around the pipe to a depth of at least 150 mm below the bottom of the pipe and up to the springline of the pipe. Install rubber manhole adapter rings on all plastic pipe installed in the manhole base.
- (d) Invert elevations of pipes at the manhole shall be checked by the Contractor prior to and following placement of base concrete around the pipe. Variations in manhole inverts from

established grade or elevation shall be corrected.

6.B.4.2 Precast Manhole Bases

- (a) Installation of precast manhole bases shall conform to Section 6B.4.1.
- (b) Precast manhole based shall be placed on 150 mm thick base of 40 mm drainrock.

6B.4.3 Manhole Channeling

- (a) Manhole channeling shall be constructed as shown on the standard drawings. The channeling shall be shaped and finished to provide smooth passage for the sewage in order to minimize head losses and deposits at bends and at junctions. The drop from inlet to outlet must be provided as shown on the drawings.
- (b) Channels shall be accurately formed. The practice of forming channels roughly to shape and finishing with mortar cement will not be permitted. The channels must be steel trowel finished.
- (c) Benching in manholes shall be sloped to drain as specified on the standard drawings. Prior to curing, the concrete benching shall be given a broom finish to produce a non-skid surface.
- (d) Where connecting to an existing main, the concrete channeling and benching may be formed around the existing pipe. The new channel shall then be cut out of the existing pipe and the concrete finished to conform to a standard manhole.
- (e) Branch lines entering the manhole shall be channeled to join the main sewer at an angle with the flow that is less than 90 degrees.

6B.4.4 Precast Manhole Sections

- (a) Manholes must be constructed so as to ensure that there is no infiltration or exfiltration.
- (b) All pipes entering manholes must be sealed using approved water stop gaskets installed in accordance with manufacturer's recommendations.
- (c) Manholes and other precast sections shall be joined and sealed using cement mortar, mastic sealer or rubber gaskets to produce a watertight joint.
- (d) Where cement mortar is used a layer of mortar shall be placed on the tongue of each section prior to lowering the following section into place. All lifting holes shall be lugged with cement mortar and finished flush with the manhole wall. The outside surface of the joint shall be sealed with an asphalt emulsion treatment or approval equal. The interior joints are to be grouted.
- (e) Where rubber gaskets or mastic sealers are used, installation must be in strict accordance with manufacturer's recommendations to ensure that a watertight joint is achieved. The

interior joints are to be grouted.

**6B.4.5 Manhole Steps**

- (a) Manhole steps shall be installed in manhole sections by the manufacturer unless circumstance dictates otherwise in which case approval must be received from the Consulting Engineer.
- (b) The distance from the top of the casting and lid, to the first manhole step shall conform to Workers Compensation Board requirements.

**6B.4.6 Frames and Covers**

- (a) Set manhole frames by firmly embedding in mortar on a minimum of 1, maximum of 3 courses of bricks or precast concrete riser rings, or cast-in-place form system with due regard to maximum distance to the first step.
- (b) The contractor may use precast concrete rings instead of concrete bricks to bring the manhole frames up to grade. The rings shall be laid in common bond with raked mortar joints and shall be faced with mortar at the entrance of the manhole.
- (c) Heavy duty frames and covers, as specified on the standard drawings, shall be installed on manholes and cleanouts. Low profile frames and covers shall only be used in special circumstances as approved by the Engineer.

**6B.4.7 Drop Structures**

Manhole drop structures shall be constructed as shown on Standard Drawings.

**6B.4.8 Stubs**

Blind stub sections for connection of future sewers and service connections to the manholes shall be installed where shown on the construction drawings and as directed by the Consulting Engineer. Stubs shall be as long as determined by the Engineer. Each stub shall be plugged with a removable, watertight plug as shown on the construction drawings. Where stubs are installed, the bottom of the manhole shall be channeled to the stub entrance.

**6B.4.9 Cleanouts**

Cleanouts shall be installed using the above specifications and information as shown on the standard drawings.

**6B.4.10 Catchbasins**

- (a) Catchbasins shall be installed in accordance with the Standard Drawings.
- (b) Catchbasin leads taken into manholes shall be benched in the same manner as main line piping.

- (c) Catchbasin grates are to be set 20 mm below the gutter line. The gutter and blacktop are to be shaped to form a dish around the inlet.
- (d) Construction and finishing of catchbasins shall be the same as for manholes.

6B.5 **SERVICE CONNECTION INSTALLATION**

- 6B.5.1 Service connections shall be installed in accordance with Standard Drawing D5
- 6B.5.2 Standards for excavation, bedding and backfilling of service connections shall be in accordance with Section 3.
- 6B.5.3 Service connection installations shall conform to the specific sizes, locations and grades indicated on the design drawings and the general requirements noted below:
  - (a) Minimum grade for a 100 mm service shall be two percent; minimum grade for a 150 mm service shall be one percent.
  - (b) Minimum cover on service shall be 1.0 m unless otherwise approved by the Engineer.
  - (c) Where horizontal bends are required in the service pipe these shall be made with long radius bends.
  - (d) Where a horizontal bend greater than 45 degrees is required, a cleanout shall be constructed.
- 6B.5.4 Services shall be extended 2.0 m into the lot in order to prevent undermining of the boulevard and to protect cleanout when connecting to service.
- 6B.5.5 The ends of the service pipes shall be marked with a 50 mm x 100 mm (2 x 4) stakes with the depth to invert indicated on the stakes. Storm drain connections shall be identified by painting the stake green.
- 6B.5.6 The connection to the main shall be made with 45 degree "Y" branches installed during construction of the main sewer. Connections onto existing sewer mains will be done by municipal personnel unless otherwise approved by the Engineer.

6B.6 **NOTIFICATION TO TOWN OF LADYSMITH**

- 6B.6.1 The Engineer shall be given 48 hours notice of all tests and flushing.
- 6B.6.2 All testing and flushing shall be performed in the presence of the Consulting Engineer and a Municipal Inspector.

6B.7 **CLEANING AND FLUSHING**

- 6B.7.1 On completion of storm sewer pipe installation, the pipe shall be cleaned to the satisfaction of the



Engineer by power flushing with water to remove all foreign matter.

6B.7.2 A silt trap shall be provided at the downstream manhole for removal of the foreign material.

6B.8 **VIDEO INSPECTING MAINS**

6B.8.1 For gravity sewers, other than service connections, the contractor shall arrange for video inspection to check alignment, grade and condition of the main sewer pipe. Inspection shall be carried out by pulling or pushing a video camera through the sewer pipe in the presence of a Municipal Inspector.

6B.8.2 The inspection shall include the preparation of a VHS tape record and a pipe condition report. The pipe condition report shall be in accordance with Section 6B.11. The contractor shall submit the VHS tape and pipe condition report to the Consulting Engineer.

6B.8.3 The Consulting Engineer shall review the VHS tape and pipe condition report and provide certification that the condition of the installed pipe is accurately recorded and the pipe installation meets the Town of Ladysmith Standards and Specifications.

6B.8.4 The VHS tape, pipe condition report and certification shall become the property of the Town of Ladysmith.

6B.8.5 Variations in line or grade of pipe, from that established by the Consulting Engineer prior to installation, and any jointing, pipe cleaning, or other deficiencies discovered during the inspection, shall be rectified. Re-inspection of the pipe may be required by the Engineer.

6B.8.6 During this test, manhole construction and invert elevations shall be checked and any variations from the established grade, drawings or specifications shall be rectified.

5B.8.7 If directed by the Engineer, the contractor shall arrange for a re-inspection of the pipe for the warranty inspection one month prior to the end of the maintenance period.

6B.9 **MANHOLE TESTING**

Manholes shall be inspected visually for infiltration. Where required by the Engineer, manholes shall also be tested for exfiltration to the same standard as required for sanitary sewers.

6B.10 **SMOKE TESTING**

6B.10.1 If required by the Engineer, the Consulting Engineer shall arrange for smoke testing of all installed gravity sanitary mains in the presence of a Municipal Inspector.

6B.10.2 The Consulting Engineer shall provide as-built service location information prior to smoke testing.

6B.10.3 Cross-connections noted during the smoke testing shall be corrected and the as-built service location information revised.

6B.11 **PIPE CONDITION REPORT FORMAT**

- 6B.11.1 Reference plans shall accompany reports with manholes labeled, and inspected sections highlighted. Manhole numbering shall conform to the construction drawings, or if available, Town of Ladysmith manhole numbers.
- 6B.11.2 All sewer defects shall be photographed and included with the report.
- 6B.11.3 The following information shall be included with the report:
- (a) Date of Survey
  - (b) Report number and tape number
  - (c) Pipe diameter, material and use
  - (d) Manhole numbers and length of section
  - (e) Direction of camera travel
  - (f) Street name
  - (g) Location of all service wyes to the nearest 0.1 metre
  - (h) Pipeline data including:
    - (i) Cleanliness, general condition and damaged areas
    - (ii) Alignment, grade, pipe profile and areas of water ponding
    - (iii) Infiltration, leaking or separated joints, root intrusion or pipe blockages
    - (iv) Protruding or damaged services, and type of service connection
    - (v) Other comments and observed conditions not suitable for acceptance by the Town of Ladysmith
    - (vi) Location of all unacceptable conditions by stationing from manhole to the nearest 0.1 metre and position as per a clock face in the direction of the camera view. Photographs shall be coordinated to the report by reference numbers.