

NOTES:

- 1. CUL-DE-SAC CURB TO BE MOUNTABLE (Drg C.1) TILTED TO DRAIN TO ROAD 4. BRICKS TO BE LAID IN HERRING BONE MEDIAN CURB TO BE NON-MOUNTABLE (Drg C.3) ANCHORED TO ASPHALT
- 2. BASE MATERIALS UNDER PAVERS (compacted thickness)
 - a) 50mm SAND
 - b) 100mm CRUSHED GRAVEL
 - c) 250mm PIT RUN GRAVEL
- 3. PAVERS TO BE SUPPLIED BY ABBOTSFORD CONCRETE PRODUCTS LTD. UNLESS APPROVED OTHERWISE

STYLE - STANDARD


COLOUR - RED

SIZE - 225mm X 112.5mm

THICKNESS - 80mm ON CENTRE ISLANDS

- 60mm ON MEDIANS

- PATTERN
- 5 FILLING SAND TO BE POLYMER
- 6 TREE GRATE TO BE 900 Ø ALUMINUM OR CAST-IRON LOCKING TYPE
- 7 TREE TYPE AS PER TOWN OF LADYSMITH TREE GUIDE OR LANDSCAPING PLAN



ROAD CENTRE MEDIANS AND CUL-DE-SAC ISLANDS

DATE: APRIL 2008 APP. BY: DRAWING No. REV. R12 01